

Local Safety Schemes Programme

Refer to RS12a - Procedure for assessing Local Safety Schemes; and Walsall Road Safety Strategy

Schemes highlighted for delivery as part of LSS programme or Other works

Reserve schemes

Schemes highlighted for future programme

Rank	Route	Section	Overall Score (2020)	Star Rating (2020)	Total cost of prevention (2020)	Key Issues	Scheme description	Scheme cost	FYRR (Calculated 40% reduction)	Comments	Status
1	Cavendish Road inc Beechdale 20mph Signed only	Blowich La to Stephenson Ave	101.91	1 Star	£1,261,872	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, children, and pedestrians; RTC's at jct with Blowich Lane and spread along route	Introduction of speed cushions along Cavendish Rd; priority build outs to improve pedestrian crossing points - review speed limit	£84,480	199%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
2	Walstead Road West	Brockhurst cresc to Hawthorne Rd	82.45	1 Star	£841,248	High collision rates, High KSI rate, Medium vulnerable road user rates for child KSI & casualties, pedestrians, and Drivers 20-29; RTC's at the following junctions: West Brom Rd and frontage of Joseph Leckie	Introduction of pedestrian islands at junction and upgrade signalling eqpt; Install new zebra crossing outside Joseph Leckie, (completed as part of S106) review signing, and road marking	£110,370	118%	Scheme cost excludes costs to introduce a new Zebra crossing as S106 funding available to installed near Pattison St; Linked to future development of WATMOS site	Programmed 2021/22
3	Field Road, Blowich	B4210 High Street to A4124 Lichfield Road	82.00	1 Star	£1,787,652	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, Drivers 20-29, and Passengers 15-24; Outside Blakenhall Heath Jnr; RTC's at Victoria Ave, Ingram Rd, Hamilton St, Chantry Ave & Field Ct	Upgrade existing both Zebra crossings to LED, Introduce speed cushions and traffic splitter islands at key junctions identified, improve lining and signing  Targeted education campaign	£155,430	153%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
4	Ablewell Street-Springhill Road	Bridge Street to Sutton Road	78.71	2 Star	£1,156,716	Medium collision rates, High KSI rate, Medium vulnerable road user rates for P2W's, Cyclists, Child casualties, pedestrians and Drivers 20-29; RTC's at the following junctions:Slways to Pool St, Lwr Rushall St	Subject to Sprint consultation and development plan	£0	#DIV/0!	Linked to Sprint	TRWM - Programmed
5	A4148 Bescot Road / Wallows Lane	Whole	73.53	2 Star	£1,787,652	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, children, pedestrians, young pedestrians, and Drivers 20-29; RTC's at Dickenson Ave & Bescot Rd Rdbt;	Warning VAS on each approach to roundabout; upgrade chevron signs; build-out kerb line on Wallows Lane approach; Review signal operation at Dickenson Ave jct; Targeted education campaign	£70,785	337%	Scheme deferred to 2021/22 consultation complete delivery scheduled for Q2; Monitor as part of annual review	Approved - Planned 2021/22
6	Wednesbury Road, Caldmore	A4148 Bescot Road to Bridgeman Street	72.32	2 Star	£2,944,368	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, Cyclists, Child casualties, pedestrians and Drivers 20-29; RTC's at the following junctions: Corporation St, Tasker St, Vicarage Place and Bridgeman St	Narrow Wednesbury Road near Glebe centre, Upgrade Zebra near Vicarage Pt, Upgrade Zebra on Vicarage Pt, introduce table top junction with Vicarage Place, VASS, HFS, built out and lining; Review traffic signals at Corporation Street	£139,630	281%	Section Hillary Street to Milton Street treated as part of LSS Programme 2016/17	Programmed 2021/22
7	A4148 Broadway north	Whole	66.51	2 Star	£2,839,212	Medium collision rates, High KSI rate, High vulnerable road user rates for P2W's, children, pedestrians, young pedestrians Drivers 20-29, and Passengers 15-24; Excessive speed and anti-social behaviour	Introduction of Average Speed Enforcement planned March 2019  Publicity	£47,481	797%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
8	A4148 Pleck Road	A4038 to A454	64.62	2 Star	£2,523,744	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, children, pedestrians and Drivers 20-29; Excessive speed and anti-social behaviour	2no. VASS, pedestrian refuges, buildouts, new roadmarking layout; Guide markings through Moat Rd/Pleck Rd junction with HFS on approach. Improved warning and directional signs. Review of operation jct with St Johns Rd  Targeted education campaign	£201,650	167%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
9	A4124 - Lichfield Road / Near Academy	Blowich	63.73	2 Star	£2,418,588	High collision rates, High KSI rate, High vulnerable road user rates for All casualties, P2W's, Cyclists, Child KSI, children, pedestrians, young pedestrians Drivers 20-29, and Passengers 15-24;	2 no. VASS, Provide build-outs and HFS on pedestrian crossing outside Academy. Wided footway towards Field Road junction.	£60,720	531%		Reserve
10	A454 Wolverhampton Road	M6 J10 to 100m west Pleck Road	63.54	2 Star	£2,944,368	High collision rates, High KSI rate, High vulnerable road user rates - cyclists, child casualties, Pedestrians, Pedestians 5-19, and Drivers 20-29; RTC's at the following junctions: Tempus Dr, Lane Ave, Alumwell Rd and Raleigh St;	Review pedestrian movements and guardrail provision at Lane Ave & Alumwell Rd, Upgrade pedestrian crossing at Raleigh Street, Signing and lining	£148,720	264%	Linked to Major Scheme development for M6 Jct 10 & Blox La/Tempus Dr, Crossing at Raleigh Street to be upgraded through NPIF2 (Feb 2020)	Approved - Currently on site
11	Walker Road	Ash St to Harden Road;	63.48	2 Star	£946,404	High collision rates, Med KSI rate, High vulnerable road user rates for All casualties, P2W's, Drivers 20-29, and Passengers 15-24;	Install speed cushions and pedestrian refuges	£83,160	152%		Reserve
12	A4038 - Walsall Rd	Darlaston Road to B4200 Park Lane	62.30	2 Star	£1,577,340	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, child casualties, pedestrians, pedestrians 5-19 and Drivers 20-29; RTC's at the following junctions: Salisbury St, Old Park Rd, Darlaston Rd	Introduce ghost right turns with traffic islands at Salisbury & Old Park Rd; review signal timings, signing and road markings	£76,560	275%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
13	B4154 Norton Road(2)	Canal Bridge to Vicarage Road	61.69	2 Star	£1,577,340	Medium collision rates, High KSI rate, Medium vulnerable road user rates for P2W's, Cyclists, Child casualties, pedestrians and Drivers 20-29; RTC's at the following junctions:Vicarage Rd, High St	Review signal operation at Vicarage Rd jct, Upgrade extg pedestrian refuge near Saton St to controlled crossing, review highway layout near Station St, improve road markings and road signs	£102,630	205%	Linked to Yorks Bridge improvements; Changes to signals at Vicarage Rd scheduled for Mar 20	Future programme
14	Lucknow Road	Spring Lane to Canal Bridge	61.47	2 Star	£736,092	High collision rates, Medium vulnerable road user rates for All casualties, P2W's, Child KSI, young pedestrians and Drivers 20-29;	Scheme details to be confirmed		#DIV/0!		Future programme
15	B4152 Salters Road Northgate	Whole	61.22	2 Star	£1,577,340	Med collision rates, Med KSI rate, High vulnerable road user rates for P2W's, Cyclists, Drivers 20-29; Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
16	A4038 - Moxley Rd	Moxley junction to A462 Darlaston Rd	60.64	2 Star	£1,472,184	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, cyclists, children, pedestrians, young pedestrians and Drivers 20-29; RTC's at Wolverhampton St and Dangerfield La jcts; single vehicle collisions;	Improve signing, lining, HFS and Wolverhampton Street and VASS/ Enhanced Watchman on Pinfold St; improve pedestrian facilities, improve signing and lining  Targeted education campaign	£95,592	205%	Budget £95,592 slipped from 2020/21 LSS Programme, additional budget required to support wider scheme. Linked to Iron Park development; linked to Wolverhampton Street delivered through Promotion of Community H&S	Approved - Planned 2021/22
17	A4148 Broadway west	Whole	59.60	3 Star	£1,051,560	Medium collision rates, High KSI rate, High vulnerable road user rates for child casualties, pedestrians, and pedestrians 5-19; RTC's at the following junctions: Bescot Cresc	Junction upgrade at Bescot Cres being implemented Mar 2020 as part of NPIF2	£250,000	56%	Bescot Crescent junction redesigned as part of NPIF 2	Implemented 20/21
18	A4124 - Lichfield Road / Pelsall Road	B4154 Norton Road to Clayhanger Lane	59.08	3 Star	£1,472,184	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
19	A34 Birmingham Road	A4148 Broadway to Bell Road	58.86	3 Star	£630,936	Medium collision rates, High KSI rate, High vulnerable road user rates for P2W's, children, pedestrians, young pedestrians Drivers 20-29, and Passengers 15-24;	Introduction of Average Speed Enforcement planned Spring 2020  Publicity	£33,691	250%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
20	Blakenhall Lane, Blakenhall	B4210 High St to Blakenhall Heath	58.57	3 Star	£420,624	High collision rates, High vulnerable road user rates for All casualties, Drivers 20-29;	Scheme details to be confirmed		#DIV/0!		Future programme
21	B4464 - Wolverhampton Road west	Whole	58.30	3 Star	£1,787,652	High collision rates, High vulnerable road user rates for P2W, child casualties, and car passengers 15-24; RTC's at the following junctions:Churchill Rd, Warwick Ave, The Crescent	Major scheme development	£0	#DIV/0!	Linked to major sustainable transport corridor improvements CWC/Walsall	Other development
22	A462 - Midland Rd	Bliston Lane to The Green	57.79	3 Star	£736,092	Med collision rates, High KSI rate, High vulnerable road user rates for All casualties, P2W's, Cyclists, and Passengers 15-24;	Scheme details to be confirmed		#DIV/0!		Future programme
23	B4210 Blowich Road / High Street	Day Street to A34	57.76	3 Star	£5,573,268	High collision rates, High KSI rate, High vulnerable road user rates - all groups; Section Hall St to Day Street, Proffitt St, Forest La, Beeches Rd, Leamore La/Harden Rd, High St	Improved pedestrian facilities and junction improvement near Forest La, build outs, improved lining signing, junction improvement Proffitt Street/ Hospital Street & section Hall St to Day St; Refuge, VASS, HFS, roadmarkings, buildouts, kerbing, Review signals at Harden Rd ban outbound right turn to Harden Rd; 20mph speed limit on High St (Link to A34 High St)	£589,517	126%	Review maintenance programme to link in with resurfacing programme  Consider as phased implementation	Future programme
24	A4038 - Darlaston Rd	Park Lane to Old Pleck Road	57.45	3 Star	£1,997,964	Medium collision rates, High KSI rate, High vulnerable road user rates - All P2W, child casualties, and Pedestrians 5-19; RTC's at the following junctions: Old Heath Rd, east Cemetery Rd, Reservoir Pt, Scarborough Rd and Wellington St	Centre hatching and pedestrian refuges, provide protected parking areas, junction treatment (build-outs), 2xVASS, review road marking and signage; (New signal junction Reservoir Pt, new arm at Cemetery Rd jct and new signal junction near The Globe Inn)	£75,900	351%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
25	B4464 - Somerford Pt / New Road	Whole	55.93	3 Star	£630,936	High collision rates, High KSI rate, High vulnerable road user rates for P2W's, and pedestrians;	Scheme details to be confirmed		#DIV/0!		Future programme
26	A4031 West Bromwich Road	Broadway to Borough Boundary	55.63	3 Star	£1,261,872	Med collision rates, High KSI rate, High vulnerable road user rates for All casualties, children, young pedestrians and Drivers 20-29;	Narrowing dual carriageway, improved lining, roundabout at Jct with Bell La, Watchman system for inbound		#DIV/0!	Scheme delivered; Monitor as part of annual review	Future programme

27	A4148 Littleton Street (Various)	Lichfield St to Pleck Road	54.70	3 Star	£3,470,148	High vulnerable road user rates for P2W's, cyclists, pedestrians, child pedestrians, Drivers 20-29 and Passengers15-24; RTC's at the following junctions: Pleck Rd, Birchills St, Green La, Hatherton St and The Arboretum;	Introduce pedestrian countdown timers; junction improvements; yellow boxes; increase capacity at Hatherton St jct;	£237,000	195%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
28	B4154 Bosty Lane	A454 Walsall Road to Barr Common Road	54.57	3 Star	£210,312	High KSI rate, High vulnerable road user rates for Drivers 20-29. RTC's at the following junctions: Barr Common Rd;	Centre hatching, 2 x watchman, improve road markings and signs	£89,100	31%	None	Future programme
29	Bescot Crescent	Broadway West to Brockhurst Cresc	54.20	3 Star	£946,404	Excessive speed Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
30	B4210 Broad Lane	Whole	54.02	3 Star	£946,404	High collision rates, High KSI rate, High vulnerable road user rates for children casualties, child pedestrians 5-19, and Drivers 20-29; RTC's at the following junctions: Baytree Rd	Introduce centre hatch, improve road signs, VASS, pedestrian refuge	£53,460	236%	None	Future programme
31	A454 Little Aston Road Section 1	Leighswood Road to Branton Hill	53.00	3 Star	£315,468	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
32	B4590 Bliton Lane	The Keyway to Owen Road	52.43	3 Star	£420,624	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
33	A34 Green Lane - Somerfield Rd - High St	Whole	51.40	3 Star	£4,521,708	Medium collision rates, High vulnerable road user rates for All cyclists, child casualties, pedestrians, child pedestrians 5-19, and car passengers 15-24; Medium rates for Drivers 20-29; RTC's at the following junctions: Stephenson Ave, Leamore Lane, High St	Undertake Route Study to identify improvements	£5,000	12058%	None	Future programme
34	Lower Rushall Street, Walsall	A4148 Broadway North to Ablewell Street	51.20	3 Star	£736,092	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
35	B4210 Sandbank & Elmore Green	Whole	50.96	3 Star	£1,051,560	High collision rate, High KSI rate, High vulnerable road user rates for P2W, child casualties, pedestrians, child pedestrians 5-19, Drivers 20-29 and car passengers 15-24; RTC's at the following junctions: Alfred St, Station St	Junction improvement at Station St, and Church Moat Way, route treatment measures incorporating centre hatch, traffic splitter islands	£45,210	310%	None	Future programme
36	B4154 Beacon Road(2)	Old Hall Lane to Queslett Road	50.71	3 Star	£525,780	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
37	A34 Birmingham Road	Bell Road to Borough Boundary	50.63	3 Star	£1,051,560	High collision rates, High KSI rate, High vulnerable road user rates for Drivers 20-29. Excessive speed and anti-social behaviour	Introduction of Average Speed Enforcement planned Spring 2020 Publicity	£33,691	416%	Budget contractually committed	Future programme
38	A462 - Sandbeds Rd / Clarkes Lane	Bentley Lane to B4464 Wolverhampton Road west	50.29	3 Star	£3,364,992	High collision rates, High KSI rate, High vulnerable road user rates for children casualties, child pedestrians 5-19, and Drivers 20-29; RTC's at the following junctions: Stroud Ave	VASS near jct with Stroud Ave	£20,000	2243%	None	Future programme
39	B4154 Walsall Road	Whole	49.21	3 Star	£420,624	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
40	A452 Chester Road High Street	Coppice Lane to A461 Lichfield Road	48.88	3 Star	£1,261,872	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
41	A4041 Queslett Road	Whole - Walsall side only	48.79	3 Star	£1,156,716	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
42	B4464 - Walsall Street / Walsall Road	Whole	48.79	3 Star	£1,577,340	High collision rates, High KSI rate, High vulnerable road user rates for all casualties and Passengers15-24; RTC's at the following junctions: Gypsy La, Bham St, Fletchers La and The Crescent	Upgrade zebra near St Giles, Upgrade zebra near Fisher Street, Junction improvement at Bham St, Junction improvement at Gypsy Lane, signing and lining, build outs, Review signals at The Crescent and usage of Walsall Rd near Guru Nanak	£98,670	213%	Linked to Major scheme for Sustainable Travel corridor linking Walsall to Wolverhampton	Future programme
43	A462 - The Green	Midland Rd to Pinfold St	48.57	3 Star	£630,936	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
44	A454 Aldridge Road	Fernleigh Road to Longwood Lane	48.50	3 Star	£420,624	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
45	A4148 Broadway	Whole	48.12	3 Star	£946,404	Medium collision rates, High KSI rate, High vulnerable road user rates for P2W's, child KSI, child casualties, child pedestrians, Drivers 20-29 and Passengers15-24; RTC's at the following junctions: West Brom Rd	Improved pedestrian facilities across Broadway near Weston Rd widen central reservation	£88,440	143%	None	Future programme
46	A461 Lichfield Road Section 3	100m east Chester Road to boundary	48.00	3 Star	£0	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
47	B4154 Barr Common Road	Whole	48.00	3 Star	£0	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
48	B4138 - Thornhill Road	Whole	47.56	3 Star	£315,468	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
49	B4154 Daw End Lane	A461 Lichfield Rd to A454 Walsall Rd	47.48	3 Star	£420,624	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
50	A4124 - Lichfield Road / Sneyd Lane	Borough Boundary to A34 High Street	47.02	3 Star	£1,261,872	High collision rate, High KSI rate, High vulnerable road user rates for P2W, Child KSI, children casualties, child pedestrians 5-19, Drivers 20-29 and car passengers 15-24; RTC's at the following junctions: The Gate Island, Sandingham Ave	Undertake Route Study to identify improvements	£5,000	3365%	None	Reserve
51	St Annes Rd - Albion St	B4464 to Bloxwich Rd South	47.00	3 Star	£1,577,340	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
52	B4151 Foley Road east	Whole	45.98	3 Star	£210,312	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
53	A462 - Bliton Lane	Wolverhampton Rd West to Owen Rd	45.24	3 Star	£946,404	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
54	B4155 Lichfield Road	Canal bridge to Boundary	45.19	3 Star	£420,624	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
55	Victoria Ave, Blakenhall	A34 High St to Blakenhall Heath	45.10	3 Star	£525,780	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
56	B4484 Pinson Road / Field Street	Sommerford Place to Moat Street	44.11	3 Star	£105,156	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
57	A41 High Street	Moxley junction to Borough Boundary	44.00	3 Star	£630,936	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
58	A462 - Essington Road	Sneyd Lane to A4124 Lichfield Road	43.59	3 Star	£736,092	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
59	B4484 - Rose Hill	Whole	43.43	3 Star	£420,624	High collision rates, High KSI rate, High vulnerable road user rates for cyclists and pedestrians; Longacre junction RTC cluster and junction with Walsall Road; Parking issues along route	Remark carriageway, introduce mini island at Longacre, VASS, formalise on street parking, review kerbing and guardrail at Walsall Road junction	£80,800	69%	Linked to Willenhall Station proposal	Future programme
60	A5 Watling Street	Whole	43.33	3 Star	£1,261,872	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
61	Leamore Lane, Leamore	Bloxwich Lane to A34 Somerfield Road	43.05	3 Star	£1,051,560	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
62	A454 Melish Road	A461 Lichfield Road to Fernleigh Road	42.98	3 Star	£315,468	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
63	Bentley Lane & Hollyhedge Lane, Birchills	Bloxwich Lane to A454 Wolverhampton Road	42.79	3 Star	£630,936	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
64	A462 - Darlaston Rd	Walsall Rd to Borough Boundary	42.00	3 Star	£420,624	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
65	A452 Chester Road urban	50m north of Raglan Close to Borough Boundary	40.17	3 Star	£1,367,028	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
66	Corporation Street -Caldmore Green - West Bromwich Street	Wednesbury Rd to Vincent Street	40.00	3 Star	£1,682,496	High collision rate, High KSI rate, Medium vulnerable road user rates for All cyclists, and pedestrians; RTC's at the following junctions: Caldmore Green	Speed cushions between Wednesbury Rd and broadway, raised table at Caldmore Green, review pedestrian facilities	£120,000	187%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
67	B4152 Brownhills Rd Lindon Road	Whole	39.72	4 Star	£525,780	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
68	B4151 Sutton Road West	Broadway to Daffodil Road	39.00	4 Star	£315,468	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
69	Aldridge Road, Streetly	B4151 Beacon Hill to A4041 Queslett Road	38.00	4 Star	£525,780	High KSI rate, High vulnerable road user rates for Drivers 20-29. RTC's at the following junctions: Queslett Rd, Bridle La, Hundred Acre Rd; Excessive speed and anti-social behaviour	Introduce 2x watchman signs on approach to Bridle La and Hundre Acre Road; Hedge trimming and increase visibility splay at Bridle La, signing and lining (SLOW, EoC, Remark), Bollards to highlight junctions, pedestrian crossing points using priority chicanes x3	£125,070	56%	None	Future programme
70	B4151 Sutton Road East	Skip Lane to Beacon Road	37.06	4 Star	£841,248	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
71	A41 Black Country New Road	Moxley junction to Borough Boundary	36.91	4 Star	£105,156	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
72	A463 Black Country Route - section 1	Borough Boundary - Midland Road	36.82	4 Star	£736,092	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
73	A4124 - Pelsall Road	B4154 Clayhanger Lane to A452 High Street	36.31	4 Star	£736,092	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
74	A4444 Black Country New Road	Borough Boundary - Moxley junction	36.00	4 Star	£105,156	Excessive speed and anti-social behaviour	Introduction of Average Speed Enforcement planned Spring 2020 Publicity	£43,893	32%	Scheme delivered; Monitor as part of annual review	Implemented 20/21
75	A461 Lichfield Road Section 1	Broadway to Daw End Lane	35.90	4 Star	£2,103,120	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
76	A461 Lichfield Road Section 2	Daw End Lane to Chester Road / High Street	35.08	4 Star	£2,734,056	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
77	A4098 Great Bridge Road	Whole	35.00	4 Star	£105,156	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
78	B4154 Longwood Road	Whole	35.00	4 Star	£315,468	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
79	B4155 Lichfield Road	High Street to Ogley Road	35.00	4 Star	£105,156	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
80	Weston Street, Caldmore	A4148 Broadway West to Wednesbury Road	33.46	4 Star	£630,936	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
81	A454 The Keyway	Portobello Island to BCR Island	33.33	4 Star	£1,051,560	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
82	A34 Stafford Road	Whole	32.99	4 Star	£525,780	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
83	B4151 Sutton Road	Daffodil Road to Skip Lane	32.83	4 Star	£105,156	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme

84	Bloxwich Lane	Bentley Lane to Fleming Road	32.00	4 Star	£315,468	Medium collision rates, High vulnerable road user rates for cyclists, children, pedestrians, and young pedestrians;	Road markings, Speed cushions as junction protection, 20mph speed limit, raised table crossings for 3 no. extg controlled pedestrian crossings	£84,480	50%	Linked to Beechdale area wide 20mph speed limit	Reserve
85	B4154 Pelsall Lane	Whole	30.93	4 Star	£210,312	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
86	A454 Walsall Road / Aldridge By Pass	B4154 Bosty Lane to Leighewood Road	30.74	4 Star	£420,624	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
87	A454 Little Aston Road Section 2	Branton Hill to A452	30.00	4 Star	£105,156	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
88	B4151 Foley Road west	Whole	30.00	4 Star	£0	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
89	B4484 - Various (Fibbersley)	Moat Street to Borough Boundary	30.00	4 Star	£105,156	Programme to be developed Excessive speed	Scheme details to be confirmed		#DIV/0!		Future programme
90	A454 Black Country Route - section 2	Midland Road - M6 J10	29.50	4 Star	£841,248	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
91	A4124 - Lichfield Road / / Wolverhampton Road	Whole	28.50	4 Star	£210,312	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
92	Noose Lane	A454 to Fibbersley	28.05	4 Star	£630,936	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
93	A452 Chester Road north	A5 Watling Street to Coppice Lane	25.00	4 Star	£105,156	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
94	A462 - Cannock - Straight Rd	A4124 Lichfield Road to Bentley Lane	25.00	4 Star	£210,312	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
95	B4154 Beacon Road	Beacon Hill to Old Hall Lane	25.00	4 Star	£315,468	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
96	A452 Chester Road (2)	Castlehill - Back Lane	24.10	4 Star	£315,468	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
97	A452 Chester Road (1)	200m south east of A461 Lichfield Rd to Castlehill	20.00	5 Star	£0	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
98	A452 Chester Road (3)	Back Lane to 50m north of Raglan Close	20.00	5 Star	£105,156	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
99	A454 Walsall Road	Longwood Lane to B4154 Bosty Lane	20.00	5 Star	£0	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
100	B4151 Beacon Hill	Whole	20.00	5 Star	£0	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
101	B4154 Norton Road	Canal Bridge to Borough Boundary	20.00	5 Star	£0	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme
102	B5011 Ogley Road / Chase Road	Whole	20.00	5 Star	£210,312	Programme to be developed	Scheme details to be confirmed		#DIV/0!		Future programme